

REPUBLIKA NG PILIPINAS KAGAWARAN NG PANANALAPI

KAWANIHAN NG INGATANG-YAMAN

(BUREAU OF THE TREASURY)

BIDS AND AWARDS COMMITTEE Supplemental Bid Bulletin No.02-2022

SUPPLY OF LABOR, MATERIALS, TOOLS/ EQUIPMENT, AND PROFESSIONAL SUPERVISION FOR THE AUGMENTATION OF THE SECURITY SURVEILLANCE SYSTEM OF THE AYUNTAMIENTO BUILDING (ITB-41-2021-G)

April 11, 2022

This Supplemental Bid Bulletin No.02-2022 is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents.

REFERENCE	AMENDMENTS/CHANGES/ CLARIFICATIONS
Page 36	Page 36
D. PROJECT REQUIREMENTS	D. PROJECT REQUIREMENTS
1.1.1. 2MP Fixed Dome Network Camera – 103 units	1.1.1. 2MP Fixed Dome Network Camera – 103 units
WDR: At least 130 dB	WDR: At least 130 120 dB
Aperture: At least F2.0	Aperture: At least F2.0 F1.4
Page 37	Page 37
D. PROJECT REQUIREMENTS	D. PROJECT REQUIREMENTS
1.1.2. 2 MP Varifocal Bullet Network Camera – 10 units	1.1.2. 2 MP Varifocal Bullet Network Camera – 10 units
Angle Adjustments: Pan: 0° to 360°, tilt: 0° to 90°, rotate: 0° to 360°	Angle Adjustments: Pan: 0° to 360° 355°, tilt: 0° to 90°, rotate: 0° to 360°
Focus: Fixed	WDR: -Fixed Adjustable
Page 37	Page 37
D. PROJECT REQUIREMENTS	D. PROJECT REQUIREMENTS
1.1.3. 5MP Fisheye Fixed Dome Network Camera – 10 units	1.1.3. 5MP Fisheye Fixed Dome Network Camera – 10 units
Aperture: At least F1.6	Aperture: At least F1.6 F2.2
Page 38	Page 38
D. PROJECT REQUIREMENTS	D. PROJECT REQUIREMENTS
1.1.4. Pan Tilt Zoom Camera – 2 Units	1.1.4. Pan Tilt Zoom Camera – 2 Units
Field of View: H: 59.8° to 2.0° (wide-tele) V: 33.6° to 1.1° (wide-tele) D: 68.6° to 2.3° (wide-tele)	Field of View: H: 59.8° 70.3° to 2.0° 1.8° (wide-tele) V: 33.6° 42.2° to 1.1° 1.0° (wide-tele) D: 68.6° 78.3° to 2.3° 2.1° (wide-tele)

ISO 9001:2015 Quality Management System Certificate No. SCP000233Q



Page 39

D. PROJECT REQUIREMENTS

1.1.7. Industrial Monitor LED Display – 6

Video and Audio Input: HDMI x 1, DVI x 1, VGA x 1, CVBS x 1, USB x 1

Video and Audio Output: DVI x 1, VGA x 1, CVBS x 1

Energy Consumption: ≤ 230W

Page 39

D. PROJECT REQUIREMENTS

1.1.7. Industrial Monitor LED Display – 6 Units

Video and Audio Input: $\frac{\text{HDMI} \times 1, \text{ DVI} \times 1,}{\text{VGA} \times 1, \text{ CVBS} \times 1, \text{ USB} \times 1}$ **HDMI 1.4** *x* 1, **HDMI 2.0** *x* 2, **VGA** *x* 1, **Audio in** *x* 1

Video And Audio Output: $\frac{DVI \times 1}{VGA \times 1}$, $\frac{CVBS \times 1}{CVBS \times 1}$ Speaker (6 Ω 7W) x 2

Energy Consumption: ≤ 230W ≤ 145W

Page 40

D. PROJECT REQUIREMENTS

1.1.10. Network Video Recorder (NVR) – 4 Units

Alarm In/Out: 16/8

Page 40

D. PROJECT REQUIREMENTS

1.1.10. Network Video Recorder (NVR) – 4 Units

Alarm In/Out: 16/8 16/4

For guidance and information of all concerned.

ATTY. GISELA F. LOOD (Sgd.)

Deputy Treasurer of the Philippines and Chairperson, Bids and Awards Committee