



*Funding the Republic*

REPUBLIKA NG PILIPINAS  
KAGAWARAN NG PANANALAPI  
**KAWANIHAN NG INGATANG-YAMAN**  
(BUREAU OF THE TREASURY)  
Intramuros, Manila

**BIDS AND AWARDS COMMITTEE**  
**Supplemental Bid Bulletin No. 16-2023**

**December 15, 2023**

**Supply of Labor, Materials and Tools for the replacement of Floor Tiles in  
the Common Area on the Ground Floor of the Ayuntamiento Building  
(ITB-17-2024-I EPA)**

This Supplemental Bid Bulletin No. 16-2023 is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents.

REFERENCE	AMENDMENTS/CHANGES/ CLARIFICATIONS
<b>Page 8, Invitation to Bid</b>  2. The <b>BTr</b> now invites bids for the above Procurement Project. Completion of Works is required by <b>one hundred fifty (150) calendar days upon receipt of Notice to Proceed</b> . Bidders should have completed, within the <b>last three (3) years</b> from the date of submission and receipt of bids, a contract similar to the Project.	<b>Page 8, Invitation to Bid</b>  2. The <b>BTr</b> now invites bids for the above Procurement Project. Completion of Works is required by <b>one hundred fifty (150) calendar days upon receipt of Notice to Proceed</b> . Bidders should have completed, within <b>the last ten (10) years</b> from the date of submission and receipt of bids, a contract similar to the Project.
<b>Page 9, Invitation to Bid</b>  6. The BTr-BAC will hold a Pre-Bid Conference on <b>December 12, 2023, 12:00 am</b> via zoom which shall be open to prospective bidders.	<b>Page 9, Invitation to Bid</b>  6. The BTr-BAC will hold a Pre-Bid Conference on <b>December 12, 2023, 11:00 am</b> via zoom which shall be open to prospective bidders.
<b>Page 19, ITB Clause 5.2 of the Bid Data Sheet</b>  For this purpose, contracts similar to the Project refers to:  a. Retiling Projects and/or other projects with similar finishes.  b. completed within the <b>last five (5) years</b> prior to the deadline for the submission and receipt of bids.	<b>Page 19, ITB Clause 5.2 of the Bid Data Sheet</b>  For this purpose, contracts similar to the Project refers to:  a. Retiling Projects and/or other projects with similar finishes.  b. completed within the <b>last ten (10) years</b> prior to the deadline for the submission and receipt of bids.
<b>Page 34.</b> <b>Section VII. Technical Specification</b> <b>D. General Requirements</b>	<b>Page 34.</b> <b>Section VII. Technical Specification</b> <b>D. General Requirements</b>

<p><b>PART I – STANDARD REQUIREMENTS AND BIDDER’S COMPLIANCE</b>  <b>2. BILL OF QUANTITIES</b>  2.4. MATERIAL SPECIFICATIONS</p>	<p><b>PART I – STANDARD REQUIREMENTS AND BIDDER’S COMPLIANCE</b>  <b>2. BILL OF QUANTITIES</b>  2.4. MATERIAL SPECIFICATIONS</p> <p><i>Note: Additional</i></p> <table border="1"> <thead> <tr> <th>LOCATION</th><th>TYPE</th></tr> </thead> <tbody> <tr> <td>2.4.1. Ground Floor Hallway</td><td><i>Homogeneous</i></td></tr> <tr> <td>2.4.2. Marble Hallway</td><td><i>Homogeneous</i></td></tr> <tr> <td>2.4.3. Tunnel Hallway</td><td><i>Homogeneous</i></td></tr> </tbody> </table>	LOCATION	TYPE	2.4.1. Ground Floor Hallway	<i>Homogeneous</i>	2.4.2. Marble Hallway	<i>Homogeneous</i>	2.4.3. Tunnel Hallway	<i>Homogeneous</i>
LOCATION	TYPE								
2.4.1. Ground Floor Hallway	<i>Homogeneous</i>								
2.4.2. Marble Hallway	<i>Homogeneous</i>								
2.4.3. Tunnel Hallway	<i>Homogeneous</i>								
<p><b>Page 35.</b>  <b>Section VII. Technical Specification</b>  <b>D. General Requirements</b>  <b>PART II. STANDARD REQUIREMENTS AND BIDDER’S COMPLIANCE</b>  <b>1. TRACK RECORD</b>  1.2 The contractor must have satisfactorily completed a single largest similar contract with an amount of at least fifty percent (50%) of the Approved Budget for the Contract (ABC) within the last five (5) years</p>	<p><b>Page 35.</b>  <b>Section VII. Technical Specification</b>  <b>D. General Requirements</b>  <b>PART II. STANDARD REQUIREMENTS AND BIDDER’S COMPLIANCE</b>  <b>1. TRACK RECORD</b>  1.2 The contractor must have satisfactorily completed a single largest similar contract with an amount of at least fifty percent (50%) of the Approved Budget for the Contract (ABC) within the <b>last ten (10) years</b></p>								
<p><b>Page 43</b>  <b>Section VIII. BILL OF QUANTITIES</b></p>	<p><b>Page 43</b>  <b>Section VIII. BILL OF QUANTITIES</b>  <i>(See attached Revised Bill of Quantities)</i></p>								

For guidance and information of all concerned.

**EDUARDO ANTHONY G. MARIÑO III** (Sgd.)  
Deputy Treasurer of the Philippines and  
Chairperson, Bids and Awards Committee

## REVISED BILL OF QUANTITIES

<b>PROJECT TITLE: SUPPLY OF LABOR, MATERIALS, AND TOOLS FOR THE SUPPLY AND REPLACEMENT OF TILES ON THE COMMON AREAS OF THE AYUNTAMIENTO BUILDING (GROUND FLOOR HALLWAY)</b>				
<b>LOCATION : Ayuntamiento Building, Bureau of the Treasury, Intramuros, Manila</b>				
<b>BILL OF QUANTITIES</b>				
DESCRIPTION	QTY		UNIT COST	TOTAL AMOUNT
	#Units	UM		
<b>I. GENERAL REQUIREMENTS</b>				
Mobilization/Demobilization	1.00	lot		
Provision on Project Management and Supervision	1.00	lot		
Provision on temporary holding Area of Materials	1.00	lot		
Provision of site security, health and safety requirements	1.00	lot		
<b>Total Cost of General Requirements</b>				
<b>II. PROJECT PREPARATION</b>				
A. Removal of damaged tiles using applicable method				
1. Ground Floor Hallway	1,070.00	sq.m		
2. Marble Hall	180.00	sq.m		
3. Tunnel Hallway	80.00	sq.m		
B. Cleaning of the floor surface to remove all unnecessary tile adhesive residue				
1. Ground Floor Hallway	1,070.00	sq.m		
2. Marble Hall	180.00	sq.m		
3. Tunnel Hallway	80.00	sq.m		
<b>Total Cost of Project Preparation</b>				
<b>III. TILING WORKS</b>				
1. Ground Floor Hallway	1,070.00	sq.m		
60cm x 60cm Floor Tiles	3,475.00	pcs		
Tile Adhesive, 25kg/bag	172.00	bags		
Tile Grout, 2kg/bag	206.00	bags		
Cement, 40kgs	160.00	bags		
Consumables (Cleaning Tools, Sponge, Palette, Levelling Tools, etc)	1.00	lot		
2. Marble Hall	180.00	sq.m		
60cm x 60cm Floor Tiles	610.00	pcs		
Tile Adhesive, 25kg/bag	30.00	bags		
Tile Grout, 2kg/bag	36.00	bags		
Cement, 40kgs	27.00	bags		
Consumables (Cleaning Tools, Sponge, Palette, Levelling Tools, etc)	1.00	lot		
3. Tunnel Hallway	80.00	sq.m		
60cm x 60cm Floor Tiles	270.00	pcs		
Tile Adhesive, 25kg/bag	3.00	bags		
Tile Grout, 2kg/bag	3.00	bags		
Cement, 40kgs	8.00	bags		
Consumables (Cleaning Tools, Sponge, Palette, Levelling Tools, etc)	1.00	lot		
<b>Total Cost of Tiling Works</b>				
<b>TOTAL COST</b>				